

MARITIME HERITAGE CENTRE SEWER CHAMBER REPLACEMENT FALL 2016

On Time and Under Budget!

Project Overview

Work under this project consisted of three parallel sewers connecting to the existing 250mm diameter gravity sewer, as well as the 200mm and 400mm forcemains, to a vault manhole installed immediately south of the driveway to the Maritime Heritage Centre. The vault manhole accommodates the three incoming sewers and has combined them into a 600mm dia. PVC sewer which tied-in to the existing 1050mm dia. interceptor.

This site was the location the Campbell River Sewer Treatment Plant. The work was completed under a design-bid-build model. Design was completed by the City's Capital Works and Sewer Departments, and construction completed by Insituform Technologies Ltd.



Funding for the Project

The project was funded through the Sewer Capital Reserve as per the approved 2016 Capital Plan. The final total cost of design and construction works associated was \$235,398k, which was delivered under the approved budget and ahead of schedule.

If you have questions or concerns, please call us at: 250-286-5700.



For more information visit www.campbellriver.ca or contact the Project Team at:

E-mail: capitalprojects@campbellriver.ca Phone: 250.286.5700

