

# Sewermain Rehabilitation Upgrade News

May 21, 2020

## WORK TO COMMENCE SOON FOLLOWING COVID-19 DELAY

---

**2400+ lineal meters of existing sanitary sewer mains in your area.**

---

### Getting Ready for Construction

Equipment will be arriving onsite to install the new sewermain liners using trenchless technology, a cured in place pipe (CIPP) lining method. This involves working man-hole to man-hole causing less disturbance as the road does not have to be excavated.



Construction is commencing June 20, 2020 and anticipated to be complete by the end of July 2020. Most of this work will take place during the day; however, between July 2<sup>nd</sup> and 24<sup>th</sup>, there will be work taking place at night from 7:00pm to 7:00am to avoid impacts to traffic and businesses in the area.

While the work is being performed, your sanitary sewer connection may be temporarily sealed off. In advance of the work, the contractor will notify you directly if there are any disruptions to your service and will be providing you with more specific information and instructions.

### Getting Around During Construction

Insituform Technologies Ltd. will have traffic control in place ensuring safe passage for vehicles and pedestrians around the work zone at all times. There should be little traffic disruption during this work.

### How will the Provincial Health Officers orders be met?

To stop the spread of COVID-19, Insituform Technologies Ltd., the contractor performing the work, will comply with the PHO's orders.

As much as possible, the crew will maintain distance and contact from outside sources, including members of the public. If social distancing cannot be achieved, then workers will remove themselves until the area is clear of other workers or other people. If the work must proceed with persons not otherwise in the crew, then workers will ensure all appropriate PPE is being used (masks, gloves, glasses) and that all shared tools and equipment are properly sanitized before they are used and before they are put away. Workers will ensure that proper washing and disinfection is completed.

### Staying Up to Date

Further information about this project is available at [www.campbellriver.ca](http://www.campbellriver.ca) or contact the project team at:  
E-mail: [capitalprojects@campbellriver.ca](mailto:capitalprojects@campbellriver.ca) or Phone: 250-286-5700.

**Thank you for your patience as we complete this Capital Project.**



G:\Capital Works\1-Projects\1-Current\14-06 SM Replacement\Projects\Oct2020\01-Design\B-Drawings\19-510.dwg Feb 21, 2020 10:56:08am



FOR PROJECT DETAILS, REFER TO DRAWING 19-510 SHEETS 1-7 REV 4 OR LATER



City of  
**Campbell River**  
Capital Works Department

DESIGNED: DD	SCALE: 1 : 4000
DRAWN: DD	DATE: 02\18\20
CHECKED: LS	DATE: 02\18\20
APPROVED: name	DATE: 02\18\20

**SEWER REHABILITATION  
2020 CIPP PROGRAM  
LOCATION MAP**

DRAWING NO. 19-510
DISK REF. n/a
SHEET-LOCMAP #1
REV.